

Hite associates

ARCHITECTURE / PLANNING / TECHNOLOGY

ADDENDUM NO. 2

January 17, 2025

Project: Security Improvements to Warren Williams Elementary School
LEE COUNTY SCHOOLS

TO: ALL BIDDERS

The following items clarify, add to, delete from, and / or otherwise change and supersede information previously issued to you in the bidding documents for the referenced project. Please read them carefully and adjust your bid accordingly.

Please note that addendums, and all revised documents are available via Hite Associates website www.hiteassoc.com under the "Contractor Resources" link.

ADDENDUM NO. 2

1. Clarification: Specification 08870 calls out security film required as 14 mil 3M Safety and Security Film.
2. CAT6 and data circuits to be run in 1" diameter conduit raceways, all work in compliance with Division 17 specifications.
3. Power circuits shall be run in conduit raceways from new EAC doors to nearest electrical panel. MDF, IDF, and electrical panel locations were reviewed on site during the Contractor walkthrough. All work shall comply with Division 16 specifications and the current NEC.
4. Space between top of aluminum storefronts to ceilings shall be wood blocking wrapped with matching 24-gauge brake metal. Reference A-106 for similar conditions.

END OF ADDENDUM NO. 2



James G. Hite, AIA, Project Architect
Hite Associates, PC

BIDDERS PLEASE NOTE THAT REFERENCED REVISED DOCUMENTS AND DRAWING REVISIONS ARE MARKED AS SUCH ON THE REVISION BLOCK ON THE PLANS AND ARE TO BE ACCESSED ON THE HITE ASSOCIATES WEBSITE.

Revised / Added Documents:

cc: All Bidders / Chris McNeill

dist.: JGH / RBE / File: Bids & Addenda