

19 May, 2026

Addendum 2

**Mill Creek Volunteer Fire Department
Newport, NC**

The following addendum shall supersede previous information and does hereby become part of the contract documents.

- All vinyl base to be 4" vinyl cove base (0.125" thick) with prefabricated corners.
- Bracing/portal frame's location to be per PEMB design and to accommodate current floor plan design.
- Clarification: LVP to be Mannington Select-Wood, 5"x48", 2.5 mil (30 mil wear thickness). Colors to be selected from manufacturers' selections.

End of Addendum 2